



ESTIMATE



Prepared For

Ametek David Smalley

SW Construction

132 Watson Hollow Rd
West Shokan, NY 12494
Phone: (845) 399-9518
Email: swconstruction12494@mail.com
Web: swconstruction.biz

Estimate # de3

Date 02/11/2026

Business / Tax # LICENSE# 17-606

Description

Total

concrete pad estimate for connex structure

this estimate includes

Excavating a 50ft by 63ft pad 16 inches deep compacting excavated area if necessary.

Placing two 4inch drains for the possibility of water getting under the slab.

Placing 8inches of #2 crushed stone compacted for a base under slab

Placing a 6mil moisture barrier on top of crushed stone

Placing a 16inch grid of #4 rebar with 30inch laps 3inches from bottom

Two runs of #5 rebar around the outside of slab

6x6 x10 guage wire mesh on top of rebar with 6inch laps

Pouring 3500# concrete finished to sweepable finish

Placing one coat of concrete sealer when finished

this document will be considered a binding contract when signed by both parties for the work to be done as outlined in document

Samuel Wilber

Ametek David Smalley

